

TABLE OF CONTENTS

1.0	INTRODUCTION	1-1
1.1	SUMMARY OF PROPOSED ACTION.....	1-2
1.1.1	PIPELINE	1-2
1.1.2	ASSOCIATED FACILITIES	1-4
1.2	STATEMENT OF OWNERSHIP	1-4
1.2.1	APPLICANT'S NAME AND CONTACT INFORMATION.....	1-7
1.2.2	AUTHORIZED REPRESENTATIVE'S NAME AND CONTACT INFORMATION	1-7
1.2.3	CONTACT REGARDING FILING.....	1-8
1.2.4	APPLICANT'S SIGNATORIES AND PREPARER.....	1-9
1.3	MINNESOTA PUBLIC UTILITIES COMMISSION (MPUC OR COMMISSION) PERMIT PROCESS	1-10
1.4	DEPARTMENT OF STATE	1-11
2.0	BACKGROUND INFORMATION.....	2-1
2.1	HISTORY OF LINE 3	2-1
2.2	BACKGROUND OF LINE 3'S INTEGRITY MANAGEMENT PLAN	2-3
2.3	LINE 3 REPLACEMENT PROGRAM.....	2-4
3.0	PURPOSE AND NEED	3-1
4.0	PROJECT DESCRIPTION	4-1
4.1	GENERAL LOCATION.....	4-1
4.2	PROPOSED REPLACEMENT PIPELINE	4-2
4.2.1	PIPELINE DESIGN SPECIFICATIONS.....	4-2
4.2.2	OPERATION PRESSURE.....	4-3
4.3	ASSOCIATED FACILITIES.....	4-4
4.3.1	PUMP STATIONS AND LOCATIONS	4-4
4.3.2	PUMP STATION SPECIFICATIONS	4-6
4.4	ABOVE GROUND FACILITIES	4-6
4.4.1	VALVE PLACEMENT	4-6
4.4.2	LAUNCHER AND RECEIVER TRAPS.....	4-7
4.4.3	OTHER THIRD-PARTY ANCILLARY FACILITIES	4-7
4.5	GENERAL DESIGN AND OPERATIONAL SPECIFICATIONS	4-7
4.5.1	PRODUCT CAPACITY INFORMATION.....	4-8

4.5.2	PRODUCT DESCRIPTION	4-8
4.5.3	MATERIAL SAFETY DATA SHEETS	4-9
4.6	LAND REQUIREMENTS.....	4-9
4.6.1	TYPICAL PERMANENT RIGHT-OF-WAY AND TEMPORARY WORKSPACE	4-9
4.6.2	ADDITIONAL TEMPORARY WORKSPACE (ATWS)	4-10
4.6.3	ABOVE-GROUND FACILITIES	4-11
4.6.4	TRENCH DIMENSIONS	4-11
4.6.5	MINIMUM DEPTH OF COVER	4-12
4.6.6	RIGHT-OF-WAY SHARING AND PARALLELING	4-13
4.6.7	PROJECT WIDTHS	4-17
4.7	PIPELINE ESTIMATED COSTS AND ACCESSIBILITY	4-18
4.8	PROJECT SCHEDULE.....	4-19
4.9	PROJECT EXPANSION	4-19
5.0	RIGHT-OF-WAY PREPARATION AND CONSTRUCTION SEQUENCE	5-1
5.1	ENVIRONMENTAL CONTROLS	5-1
5.1.1	ENVIRONMENTAL INSPECTORS	5-1
5.1.2	EROSION AND SEDIMENT CONTROLS	5-2
5.1.3	CONSTRUCTION TIMINGS	5-2
5.2	PREPARING THE RIGHT-OF-WAY AND CONSTRUCTION SEQUENCE.....	5-2
5.2.1	SURVEY AND STAKING	5-7
5.2.2	CLEARING AND GRADING	5-8
5.2.3	SOIL SEPARATION	5-12
5.2.4	STRINGING PIPE	5-14
5.2.5	BENDING AND WELDING/COATING AND INSPECTION	5-16
5.2.6	TRENCHING AND LOWERING OF THE PIPELINE	5-19
5.2.7	BACKFILLING THE TRENCH	5-26
5.2.8	HYDROSTATIC TESTING	5-29
5.2.9	RESTORATION AND REVEGATION	5-29
5.3	OPERATION AND MAINTENANCE	5-32
6.0	ROUTE SELECTION PROCESS	6-1
6.1	LINE 3 ROUTE DEVELOPMENT PROCESS	6-1
6.2	DEVELOPMENT AND APPLICATION OF ROUTING CRITERIA	6-1
6.3	DATA COLLECTION	6-4
6.4	STUDY AREA IDENTIFICATION.....	6-4

6.4.1	WEST OF CLEARBROOK STUDY AREA (WCSA)	6-5
6.4.2	EAST OF CLEARVROOK STUDY AREA (ECSA)	6-5
6.5	STUDY CORRIDOR IDENTIFICATION.....	6-6
6.6	EVALUATION OF REPLACEMENT OPTIONS AND ROUTE VARIATIONS	6-7
6.6.1	OPTION 1 – REPLACE LINE 3 IN ITS SAME TRENCH	6-7
6.6.2	OPTION 2 – REPLACE LINE 3 PARALLEL TO EXISTING ENBRIDGE MAINLINE SYSTEM WEST OF CLEARBROOK AND FOLLOW NORTHERN ROUTE ALTERNATIVE EAST OF CLEARBROOK	6-21
6.6.3	OPTION 3 – REPLACE LINE 3 PARALLEL TO ENBRIDGE MAINLINE SYSTEM WEST OF CLEARBROOK AND FOLLOW THE SOUTHERN ROUTE ALTERNATIVE EAST OF CLEARBROOK	6-30
6.6.4	SUMMARY OF LINE 3’S ROUTE ANALYSIS	6-31
6.7	DESCRIPTION OF PREFERRED ROUTE	6-32
7.0	ENVIRONMENTAL IMPACT OF PREFERRED ROUTE.....	7-1
7.1	INTRODUCTION	7-1
7.1.1	AGENCY CONSULTATIONS AND COMMITMENTS	7-2
7.1.2	FIELD SURVEYS	7-6
7.1.3	IMPACT CALCULATIONS.....	7-11
7.1.4	ASSOCIATED FACILITIES IMPACTS.....	7-17
7.2	HUMAN SETTLEMENT	7-21
7.2.1	EXISTING ENVIRONMENT	7-21
7.2.2	CONSTRUCTION IMPACTS AND MITIGATION	7-25
7.2.3	OPERATIONS IMPACTS AND MITIGATION	7-26
7.3	TRANSPORTATION	7-28
7.3.1	EXISTING ENVIRONMENT	7-28
7.3.2	CONSTRUCTION IMPACTS AND MITIGATION	7-29
7.3.3	OPERATIONS IMPACTS AND MITIGATION	7-30
7.4	NOISE	7-32
7.4.1	EXISTING ENVIRONMENT	7-32
7.4.2	CONSTRUCTION IMPACTS AND MITIGATION	7-32
7.4.3	OPERATIONS IMPACTS AND MITIGATION	7-33
7.5	LAND USE	7-35
7.5.1	EXISTING ENVIRONMENT	7-35
7.5.2	CONSTRUCTION IMPACTS AND MITIGATION	7-43
7.5.3	OPERATIONS IMPACTS AND MITIGATION	7-50
7.6	PUBLIC AND DESIGNATED LANDS	7-54

7.6.1	EXISTING ENVIRONMENT	7-54
7.6.2	CONSTRUCTION IMPACTS AND MITIGATION	7-63
7.6.3	OPERATIONS IMPACTS AND MITIGATION	7-65
7.7	GEOLOGY.....	7-68
7.7.1	EXISTING ENVIRONMENT	7-68
7.7.2	CONSTRUCTION IMPACTS AND MITIGATION	7-78
7.7.3	OPERATIONS IMPACTS AND MITIGATION	7-80
7.8	SOILS.....	7-82
7.8.1	EXISTING ENVIRONMENT	7-82
7.8.2	CONSTRUCTION IMPACTS AND MITIGATION	7-88
7.8.3	OPERATIONS IMPACTS AND MITIGATION	7-93
7.9	VEGETATION.....	7-95
7.9.1	EXISTING ENVIRONMENT	7-95
7.9.2	CONSTRUCTION IMPACTS AND MITIGATION	7-105
7.9.3	OPERATIONS IMPACTS AND MITIGATION	7-107
7.10	WILDLIFE	7-108
7.10.1	EXISTING ENVIRONMENT	7-108
7.10.2	CONSTRUCTION IMPACTS AND MITIGATION	7-112
7.10.3	OPERATIONS IMPACTS AND MITIGATION	7-114
7.11	FISHERIES	7-116
7.11.1	EXISTING ENVIRONMENT	7-116
7.11.2	CONSTRUCTION IMPACTS AND MITIGATION	7-117
7.11.3	OPERATIONS IMPACTS AND MITIGATION	7-119
7.12	THREATENED AND ENDANGERED SPECIES	7-121
7.12.1	FEDERALLY LISTED SPECIES	7-121
7.12.2	STATE-LISTED SPECIES.....	7-122
7.12.3	NORTHERN LONG-EARED BAT	7-124
7.12.4	CANADA LYNX	7-126
7.12.5	GRAY WOLF	7-128
7.12.6	BALD AND GOLDEN EAGLES.....	7-130
7.12.7	SPRAGUE’S PIPIT	7-131
7.12.8	HENSLOW’S SPARROW	7-133
7.12.9	DAKOTA SKIPPER.....	7-134
7.12.10	POWESHIEK SKIPPERLING	7-136
7.12.11	BLANDING’S TURTLE	7-138
7.12.12	PUGNOSE SHINER	7-140
7.12.13	STATE-PROTECTED MUSSELS.....	7-141
7.12.14	WESTERN PRAIRIE FRINGED ORCHID.....	7-143
7.12.15	STATE-PROTECTED FLORA	7-144

	7.12.16 ASSOCIATED FACILITIES	7-147
7.13	GROUNDWATER RESOURCES	7-148
	7.13.1 EXISTING ENVIRONMENT	7-148
	7.13.2 CONSTRUCTION IMPACTS AND MITIGATION	7-154
	7.13.3 OPERATIONS IMPACTS AND MITIGATION	7-156
7.14	WETLANDS	7-157
	7.14.1 EXISTING ENVIRONMENT	7-157
	7.14.2 CONSTRUCTION IMPACTS AND MITIGATION	7-163
	7.14.3 OPERATIONS IMPACTS AND MITIGATION	7-169
7.15	WATERBODIES	7-174
	7.15.1 EXISTING ENVIRONMENT	7-174
	7.15.2 CONSTRUCTION IMPACTS AND MITIGATION	7-181
	7.15.3 OPERATIONS IMPACTS AND MITIGATION	7-197
7.16	CULTURAL RESOURCES	7-198
	7.16.1 EXISTING ENVIRONMENT	7-198
	7.16.2 CONSTRUCTION IMPACTS AND MITIGATION	7-202
	7.16.3 OPERATIONS IMPACTS AND MITIGATION	7-203
7.17	AIR QUALITY	7-204
	7.17.1 EXISTING ENVIRONMENT	7-204
	7.17.2 CONSTRUCTION IMPACTS AND MITIGATION	7-204
	7.17.3 OPERATIONS IMPACTS AND MITIGATION	7-205
7.18	PERMIT TABLE	7-207
8.0	PERMANENT REMOVAL OF EXISTING LINE 3 FROM SERVICE	8-1
8.1	TIMING	8-1
8.2	GOVERNING REQUIREMENTS AND SCOPE	8-1
8.3	CONTINUED MAINTENANCE OF THE RIGHT-OF-WAY	8-2
8.4	KEEPING THE EXISTING LINE 3 IN PLACE VERSUS REMOVAL	8-3
9.0	PUBLIC AND STAKEHOLDER OUTREACH EFFORTS	9-1
9.1	COMMITMENT TO PUBLIC AND STAKEHOLDER OUTREACH	9-1
9.2	OBJECTIVES OF THE PUBLIC AND STAKEHOLDER OUTREACH PROGRAM	9-3
9.3	OPEN HOUSE MEETINGS	9-3
9.4	PROJECT MAILINGS	9-12



9.5	STAKEHOLDER MEETINGS.....	9-13
9.6	OTHER OUTREACH TOOLS	9-14
9.7	NOTICE PLAN – CERTIFICATE OF NEED.....	9-14
10.0	REFERENCES	10-1

LIST OF TABLES

Table 4.2.1-1	Line 3 Replacement Project Pipe Specifications.....	4-3
Table 4.3.1-1	Existing Line 3 Minnesota Pump Stations.....	4-4
Table 4.3.1-2	Line 3 Replacement Project Minnesota Pump Stations	4-5
Table 4.3.2-1	Line 3 Replacement Project Pump Station Specifications	4-6
Table 4.4.1-1	Valve Design Parameters.....	4-7
Table 4.6.1-1	Anticipated Land Requirements	4-10
Table 4.6.4-1	Typical Trench Dimensions.....	4-11
Table 4.6.5-1	Depth of Cover Based on Location	4-12
Table 4.6.6-1	Line 3 Replacement Project – Paralleling Other Corridors West of Clearbrook.....	4-13
Table 4.6.6-2	Line 3 Replacement Project – Paralleling Other Corridors East of Clearbrook	4-14
Table 4.6.7-1	Typical Project Widths.....	4-17
Table 4.8-1	Project Schedule	4-19
Table 6.6.2-1	Routing Analysis: Parallel West of Clearbrook, Northern Route Alternative	6-22
Table 6.6.2-2	East of Clearbrook - Features Comparison of Replacement Alternatives	6-26
Table 7.1.1-1	Federal, State, and Local Regulatory Agency Consultations	7-3
Table 7.1.2-1	Status of Environmental Surveys.....	7-7
Table 7.1.3-1	Summary of Impact Calculations.....	7-11
Table 7.1.4-1	Proposed Associated Facilities for the Line 3 Replacement Project	7-17
Table 7.2.1-1	Population and Socioeconomic Conditions in the Line 3 Replacement Project Area	7-21
Table 7.2.1-2	Municipalities within 1 Mile of the Line 3 Replacement Project	7-22
Table 7.3.1-1	Number of Roads Crossed by the Line 3 Replacement Project.....	7-28
Table 7.3.1-2	Railroads Crossed by the Line 3 Replacement Project	7-29
Table 7.5.1-1	Ownership of Lands Crossed by the Line 3 Replacement Project (miles)	7-35
Table 7.5.2-1	Line 3 Replacement Project Construction Impacts by Land Cover Type	7-44
Table 7.5.2-2	Residences Within 50 and 500 Feet of the Construction Right-of-Way.....	7-49
Table 7.5.2-3	Line 3 Replacement Project Proposed Associated Facilities Construction Impacts by Land Cover Type..	7-50

Table 7.5.3-1	Line 3 Replacement Project Operations Impacts by Land Cover Type.....	7-51
Table 7.5.3-2	Line 3 Replacement Project Proposed Pump Stations Operations Impacts by Land Cover Type	7-53
Table 7.6.1-1	State Forests Crossed by the Line 3 Replacement Project	7-57
Table 7.7.1-1	Elevation within the Line 3 Replacement Project Area	7-75
Table 7.7.1-2	Mineral Resources within 1,500 Feet of the Line 3 Replacement Project	7-76
Table 7.7.1-3	Lands Leased for Mineral Exploration Crossed by the Line 3 Replacement Project	7-77
Table 7.8.1-1	MLRAs Crossed by the Line 3 Replacement Project	7-82
Table 7.8.1-2	Soil Characteristics within the Line 3 Replacement Project Construction Workspace	7-86
Table 7.8.1-3	Topsoil Depths and Slope Class within the Line 3 Replacement Project Construction Workspace	7-87
Table 7.8.1-4	Topsoil Depths on Prime Farmland in the Line 3 Replacement Project Construction Workspace	7-87
Table 7.8.1-5	Line 3 Replacement Project Proposed Associated Facilities Construction Impacts on Soils	7-93
Table 7.8.3-1	Line 3 Replacement Project Proposed Associated Facilities Operations Impacts on Soils.....	7-94
Table 7.9.1-1	Ecological Sections and Subsections of the Laurentian Mixed Forest Province Crossed by the Line 3 Replacement Project	7-96
Table 7.9.1-2	Native Plant Communities Crossed by the Line 3 Replacement Project	7-100
Table 7.9.1-3	Sites of Biodiversity Significance Crossed by the Line 3 Replacement Project	7-101
Table 7.11.1-1	Game Fish Species in the Line 3 Replacement Project Area	7-116
Table 7.11.1-2	Trout Streams Crossed by the Line 3 Replacement Project	7-117
Table 7.12.1-1	Federally Listed, Proposed, and Candidate Species and Proposed Critical Habitat in Counties Crossed by the Line 3 Replacement Project.....	7-122
Table 7.12.2-1	Element Occurrences in Minnesota’s Natural Heritage Information System Within 1 Mile on Either Side of the Preferred Route	7-123
Table 7.12.15-1	State-Threatened and State-Endangered Plant Species with Potential to Occur Within the Line 3 Replacement Project Area	7-145
Table 7.13.1-1	Wells and Boreholes Identified within 200 Feet of the Line 3 Replacement Project.....	7-150



**Enbridge Energy, Limited Partnership
Pipeline Routing Permit Application
MPUC Docket No. PL-9/PPL-15-137**

**April 2015
List of Tables**

Table 7.13.1-2	Potentially Contaminated Sites within 0.5 Mile of the Line 3 Replacement Project	7-152
Table 7.14.1-1	Wetland Bank Service Areas Crossed by the Line 3 Replacement Project.....	7-161
Table 7.14.1-2	MNDNR Public Water Wetlands and Basins Crossed by the Line 3 Replacement Project.....	7-162
Table 7.14.2-1	Line 3 Replacement Project Construction Impacts by Wetland Type	7-164
Table 7.14.2-2	Line 3 Replacement Project Proposed Associated Facilities Construction Impacts By Wetland Type.....	7-167
Table 7.14.3-1	Line 3 Replacement Project Operations Impacts by Wetlands Type	7-170
Table 7.14.3-3	Line 3 Replacement Project Proposed Associated Facilities Operations Impacts by Wetland Type.....	7-173
Table 7.15.1-1	Major Watersheds Crossed by the Line 3 Replacement Project	7-174
Table 7.15.1-2	Summary of Waterbodies Crossed by the Line 3 Replacement Project.....	7-178
Table 7.15.1-3	Impaired Streams Crossed by the Line 3 Replacement Project	7-180
Table 7.15.2-1	Proposed Horizontal Directional Drill Locations – Waterbodies.....	7-187
Table 7.16.1-1	Cultural Resources Reports Prepared for the Line 3 Replacement Project	7-199
Table 7.16.1-2	Tally of Cultural Resources Survey Acreage for the Line 3 Replacement Project	7-199
Table 7.16.1-3	Archaeological Sites Recorded during Field Surveys in 2013 and 2014 for the Line 3 Replacement Project	7-202
Table 7.18-1	Preliminary List of Government Authorities and Titles of Permits/Approvals (Minnesota Portion of Line 3 Replacement Project)	7-207
Table 9.3-1	Open House Summary.....	9-12

LIST OF FIGURES

Figure 1.0-1	Enbridge U.S. Liquids Pipeline Regional Map	1-1
Figure 1.1-1	Project Overview Map	1-3
Figure 1.2-1	Enbridge Overview Map	1-5
Figure 1.2-2	Petroleum Administration for Defense Districts	1-6
Figure 2.1-1	Overview Map of Line 3.....	2-1
Figure 2.3-1	Line 3 Replacement Program	2-5
Figure 4.1-1	Project Overview Map	4-1
Figure 5.2-1	Typical Project Construction Footprint in Upland and Wetland Areas	5-3
Figure 5.2.1-1	Right-of-Way Staking	5-7
Figure 5.2.2-1	Hydro-Axe	5-8
Figure 5.2.2-2	Typical Span Type Bridge With or Without Instream Support	5-9
Figure 5.2.2-3	Timber Mats	5-10
Figure 5.2.2-4	Typical Wetland Crossing Method.....	5-11
Figure 5.2.3-1	Topsoil Segregation	5-12
Figure 5.2.3-2	Typical Topsoil Segregation – Modified Ditch Plus Spoil Side	5-13
Figure 5.2.4-1	Pipe Loading	5-14
Figure 5.2.4-2	Pipe Stringing.....	5-15
Figure 5.2.5-1	Field Bending	5-16
Figure 5.2.5-2	Welding Shacks.....	5-17
Figure 5.2.5-3	Field Inspection.....	5-18
Figure 5.2.6-1	Lowering of the Pipeline.....	5-19
Figure 5.2.6-2	Typical Trench Breakers – Perspective View	5-21
Figure 5.2.6-3	Straw Bale Dewatering Structure	5-22
Figure 5.2.6-4	Typical Dewatering Measures	5-23
Figure 5.2.6-5	Horizontal Directional Drilling Method	5-24
Figure 5.2.6-6	Flume Method	5-25
Figure 5.2.7-1	Backfilling.....	5-26

Figure 5.2.7-2	Traffic Control.....	5-27
Figure 5.2.7-3	Road Boring	5-28
Figure 5.2.7-4	Typical Improved Road Crossing.....	5-28
Figure 5.2.9-1	Regrading.....	5-29
Figure 5.2.9-2	Erosion Control	5-30
Figure 5.2.9-3	Rock Removal	5-30
Figure 5.2.9-4	Typical Stream Bank Stabilization - Biolog.....	5-31
Figure 5.2.9-5	Restored Pipeline.....	5-32
Figure 5.3-1	Restored Pipeline Right-of-Way	5-32
Figure 6.2-1	Project Geographic Requirements	6-2
Figure 6.4-1	Study Areas.....	6-5
Figure 6.6.1-1	Same Trench Replacement.....	6-8
Figure 6.6.1-2	Typical ROW Configuration	6-9
Figure 6.6.1-3	Typical Profile of the Construction Footprint for Same Trench Removal	6-12
Figure 6.6.1-4	Typical Profile of the Construction Footprint for Same Trench Installation	6-13
Figure 6.6.1-5	Typical Construction Workspace West of Clearbrook – Scenario 1 Same Trench Replacement (North Side Workspace)	6-15
Figure 6.6.1-6	Typical Construction Workspace West of Clearbrook – Scenario 2 Same Trench Installation (South Side Workspace).....	6-16
Figure 6.6.1-7	Typical Construction Workspace East of Clearbrook – Scenario 1 Same Trench Installation (North Side Workspace).....	6-18
Figure 6.6.1-8	Typical Construction Workspace East of Clearbrook – Scenario 2 Same Trench Installation (South Side Workspace).....	6-19
Figure 6.6.2-1	Parallel Replacement West of Clearbrook and Northern Route Alternative	6-21
Figure 6.6.2-2	Northern and Southern Route Comparison Analysis	6-25
Figure 6.6.3-1	Preferred Route	6-30
Figure 6.7-1	Project Interconnections and Facilities	6-33
Map 7.1.2-1	Wetland/Waterbody and Cultural Field Survey Coverage	7-9
Figure 7.1.3-1a	West of Clearbrook Line 3 Construction and Operations Workspace in Uplands.....	7-14

Figure 7.1.3-1b	West of Clearbrook Line 3 Construction and Operations Workspace in Wetlands	7-14
Figure 7.1.3-2a	East of Clearbrook Line 3 Construction and Operations Workspace in Uplands	7-15
Figure 7.1.3-2b	East of Clearbrook Line 3 Construction and Operations Workspace in Wetlands	7-15
Figure 7.1.3-3a	East of Clearbrook Line 3 Construction and Operations Workspace in Uplands (Assumes Sandpiper is Constructed First)	7-16
Figure 7.1.3-3b	East of Clearbrook Line 3 Construction and Operations Workspace in Wetlands (Assumes Sandpiper is Constructed First)	7-16
Map 7.1.4-1	Proposed Pump Stations	7-19
Figure 7.2.1-1	Leisure & Hospitality Industry Gross Sales in Counties Crossed by the Line 3 Replacement Project	7-24
Figure 7.2.1-2	Leisure & Hospitality Industry Private Sector Employment in Counties Crossed by the Line 3 Replacement Project	7-25
Figure 7.5.1-1a	Land Ownership West of Clearbrook (Percent)	7-36
Figure 7.5.1-1b	Land Ownership East of Clearbrook (Percent)	7-36
Map 7.5.1-1	Land Ownership	7-37
Figure 7.5.1-2a	Land Cover West of Clearbrook (Percent)	7-39
Figure 7.5.1-2b	Land Cover East of Clearbrook (Percent)	7-39
Map 7.5.1-2	Land Cover	7-41
Figure 7.5.2-1a	West of Clearbrook Construction Impacts by Land Cover Type (Acres)	7-44
Figure 7.5.2-1b	East of Clearbrook Construction Impacts by Land Cover Type (Acres)	7-45
Figure 7.5.2-1c	East of Clearbrook Construction Impacts by Land Cover Type (Assumes Sandpiper is Constructed First) (Acres)	7-45
Figure 7.5.3-1a	West of Clearbrook Operations Impacts by Land Cover Type (Acres)	7-52
Figure 7.5.3-1b	East of Clearbrook Operations Impacts by Land Cover Type (Acres)	7-52
Figure 7.5.3-1c	East of Clearbrook Operations Impacts by Land Cover Type (Assumes Sandpiper is Constructed First) (Acres)	7-53
Map 7.6.1-1	Public and Designated Lands	7-55
Map 7.6.1-2	MNDNR Wildlife Management Areas	7-59
Map 7.7.1-1	Bedrock Geology	7-71
Map 7.7.1-2	Quaternary Geology	7-73

Map 7.8.1-1	Major Land Resource Area (MLRA)	7-83
Map 7.9.1-1	Ecological Provinces and Subsections	7-97
Map 7.14.1-1	Wetland Bank Service Areas.....	7-159
Figure 7.14.2-1a	West of Clearbrook Construction Impacts by Wetland Type (Acres)	7-165
Figure 7.14.2-1b	East of Clearbrook Construction Impacts by Wetland Type (Acres)	7-165
Figure 7.14.2-1c	East of Clearbrook Construction Impacts by Wetland Type (Assumes Sandpiper is Constructed First) (Acres)	7-166
Figure 7.14.3-1a	West of Clearbrook Operations Impacts by Wetland Type (Acres).....	7-170
Figure 7.14.3-1b	East of Clearbrook Operations Impacts by Wetland Type (Acres)	7-171
Figure 7.14.3-1c	East of Clearbrook Operations Impacts by Wetland Type (Assume Sandpiper is Constructed First) (Acres)	7-171
Map 7.15.1-1	Watersheds.....	7-175
Figure 8.2-1	Deactivation Process	8-2
Figure 9.3-1	Open House Meeting Flyer.....	9-4
Figure 9.5-1	Public Outreach by Type.....	9-13

APPENDICES

Appendix A	1991 Line 3 Presidential Permit
Appendix B	Project Maps
Appendix B.1	Project Overview Map
Appendix B.2	Project County Maps
Appendix B.3	Project Preferred Route Maps
Appendix C	Station Plot Plans
Appendix C.1	Donaldson Station – Station Plot Plan
Appendix C.2	Viking Station – Station Plot Plan
Appendix C.3	Plummer Station – Station Plot Plan
Appendix C.4	Clearbrook Terminal – Station Plot Plan
Appendix C.5	Two Inlets Station – Station Plot Plan
Appendix C.6	Backus Station – Station Plot Plan
Appendix C.7	Palisade Station – Station Plot Plan
Appendix C.8	Cromwell Station – Station Plot Plan
Appendix D	Pipeline Safety Report
Appendix E	Environmental Protection Plan
Appendix F	Material Safety Data Sheets
Appendix G	Typical Right-of-Way Configuration Drawings
Appendix G.1	West of Clearbrook Co-Located with Existing Enbridge Pipeline
Appendix G.2	Parallel to Foreign Utility Easement
Appendix G.3	Greenfield Right-of-Way
Appendix G.4	East of Clearbrook Co-Located with Proposed NDPC Pipeline
Appendix H	Agricultural Protection Plan
Appendix I	Same Trench Installation Typicals

Appendix I.1	Typical Construction Workspace for West of Clearbrook – Scenario 1
Appendix I.2	Typical Construction Workspace for West of Clearbrook – Scenario 2
Appendix I.3	Typical Construction Workspace for East of Clearbrook – Scenario 1
Appendix I.4	Typical Construction Workspace for East of Clearbrook – Scenario 2
Appendix J	Agency Consultation Letters from Enbridge
Appendix K	Enbridge Response to Sandpiper Comment Letters
Appendix L	Number of Roads Crossed
Appendix M	Noise Impact Analysis
Appendix M.1	Noise Impact Analysis – Donaldson Station
Appendix M.2	Noise Impact Analysis – Viking Station
Appendix M.3	Noise Impact Analysis – Plummer Station
Appendix M.4	MPCA, A Guide to Noise Control in Minnesota
Appendix N	Tables Detailing Construction and Operations Impacts
Appendix N.1	Potential Construction Impacts by Land Use and County
Appendix N.2	Operations Impacts by Land Use and County
Appendix N.3	Potential Construction Impacts by Wetland Type and County
Appendix N.4	Operations Impacts by Wetland Type and County
Appendix O	Waterbodies Crossed
Appendix P	Unanticipated Discoveries Plan
Appendix Q	Public Outreach Materials
Appendix Q.1	News Release, March 3, 2014: Enbridge to Undertake \$7 Billion Mainline Replacement Program
Appendix Q.2	Media Outlets on Enbridge News Release Distribution List
Appendix Q.3	Line 3 Replacement Project Fact Sheet
Appendix Q.4	Civil and Environmental Surveys
Appendix Q.5	Bat Survey Brochure
Appendix Q.6	Line 3 Replacement Project Introductory Packet

- Appendix Q.7** Media Advisory, November 29, 2014: Enbridge announces Line 3 Project Open Houses
- Appendix Q.8** Line 3 Replacement Project Open House Invitation
- Appendix Q.9** Line 3 Replacement Project Open House Advertisement for Newspaper Publication
- Appendix Q.10** Line 3 Replacement Project Public Outreach Meetings List